



CLIENT

Northern Powergrid

PROJECT

Secondary SCADA

LOCATION

Castleford Batch Two

SERVICES PROVIDED

Test and commission of RTU radios



NORTHERN POWERGRID (NPG) SECONDARY SCADA COMMISSION



OVERVIEW

NPg operates a ground mounted remote-control system across their distribution substation network. This system enables them to monitor plant on the distribution network and carry out remote switching from the system control centres.

To enhance the capability and capacity of this system, NPg requires the commissioning of radio equipment at strategically identified sites on the distribution network across both the NPg Northeast plc and NPg Yorkshire plc license areas. This will minimise the impact and duration of unplanned fault related loss of supplies to reduce the number of Customer Minutes Lost (CML's) and therefore support the vision of providing an excellent Customer Service.



The scope of work is to update existing equipment and software for remote-control systems aligned with the NPg Secondary SCADA project for 2022. The work is on the 11kV and 20kV ground mounted networks in both licenced areas and is a mixture of indoor and outdoor substation locations.

Work will include:

- Management of radio commissions when at the site.
- Provision of suitably skilled and authorised staff for all HV switching and commissioning-related operational activities.
- Organisation of the HV outage requests on the NPg network in the northeast. This may include IUS switching out HV circuits and issuing safety documentation where applicable.
- In Yorkshire, liaison with the NPg Telecommunications team to facilitate testing and change of the substation site radios and commissioning confirmation.
- Arrange all necessary access permissions, highlighting any substation issues where sites are inaccessible or have vegetation issues, which should be reported as part of basic housekeeping through the 159-reporting process (NPg Amp 2 View application).

Critical to the successful delivery of these works is the effective liaison with NPg's Secondary SCADA Project team, Telecommunications, Technical Service teams, and appointed third-party companies and EMR Integrated Services. IUS worked collaboratively on-site with the NPg-appointed contractors to facilitate the collective delivery of this work.







NORTHERN POWERGRID (NPG) SECONDARY SCADA COMMISSION





